



The International Maritime Transport and Logistics Conference "MARLOG 13"

# Towards \_\_\_\_\_ Smart Green Blue Infrastructure

3-5 March 2024 - Alexandria, Egypt





### Mahmoud Roushdy

Marine engineer, Hill international, North Africa

Optimization of retrofitting an anchored sheet pile quay wall using separated relieving platform






Mahmoud M. Roushdy, Mohamed E. El-Naggar, Ahmed Y. Abdelaziz




- Quay walls serve as integral components of any functioning port, providing critical infrastructure for docking and unloading vessels.
- Among the various types of quay walls, anchored sheet piles stand out as a common choice due to their durability and effectiveness in withstanding the forces exerted by the surrounding marine environment.






 An Anchored sheet pile system typically consists of a front wall, a tying system, and an anchorage system.

 Considering the swift evolution in the maritime sector, particularly concerning vessel dimensions and tonnage, the necessity to upgrade quay walls is undeniable in order to accommodate these advancements.






- A prevalent method for upgrading a quay wall, often employed in Egypt, involves constructing a new quay wall in front of the existing one, designed to withstand the additional anticipated loads.
- While effective and straightforward, this approach comes with substantial costs and reduces the available basin area within the port.





- An alternative method for upgrading an anchored sheet pile quay wall is to install a platform supported by piles, known as a relieving platform, along the apron side, separated from the existing quay wall.
- The effectiveness of this added platform in upgrading the existing quay wall to allow for deeper basins and elevated loadings was demonstrated by Roushdy et al., (2023).




Roushdy, M., Naggar, M., Abdelaziz, A.: "Numerical Investigation on Anchored Sheet Pile Quay Wall with Separated Relieving Platform". World Academy of Science, Engineering and Technology, Open Science Index 204, International Journal of Geotechnical and Geological Engineering (2023), 17(12), 182 - 200.



### **Objective of the Study**

• This study focuses on analyzing the added **platform supported on piles as an upgrade** to the existing quay wall, aiming to determine the **optimal dimensions** for maximizing the upgrade's effectiveness.





#### **Research Methodology**

- The methodology employed in this study involves numerical investigation to achieve the study's objectives, utilizing finite element analysis with PLAXIS 3D Software.
- This methodology comprises of:

Verification Phase Carried out through the utilization of **field measurements** conducted by **Endley** *et al.,* **(2000)**, the output of this step is a validated model.

#### Parametric study Phase


The validated model is expanded in a parametric study to encompass a series of models with variations in the number of piles supporting the platform, different pile sections, varied spacing between piles, piles at different bearing levels, and platforms positioned at different elevations.

Endley, S. N., Dunlap, W. A., Knuckey, D. M., & Sreerama, K. (2000). **Performance of an Anchored Sheet-Pile Wall**. In Geotechnical Measurements. Geo-Denver 2000. American Society of Civil Engineers. https://doi.org/10.1061/40518(294)14



#### **Verification Phase**

- The actual quay wall was a general cargo type situated in the Port of Freeport, Texas, USA.
- The soil encountered in the field at the vicinity of the quay wall consisted of overconsolidated clay, located approximately 9.75 m below the mean water level (MWL).
- The measurements were conducted for two phases: after backfilling (October 1986) and after finalizing the superstructure (November 1987).






## **Verification Phase – Date of Field Measurements**

#### After backfilling (OCT, 86)


#### After superstructure finalizing (NOV, 87)








### Verification Phase – Front wall





### **Parametric study Phase**

• The validated model was expanded to include two basic reference models, each featuring distinct retained soils: sandy fill and overconsolidated clay.






#### **Parametric study Phase**


The parametric study involves comparing the reference models to the refined cases of the platform with varying pile setups in order to achieve optimization using both of the retained soil types.






- 1) Effect of **increasing Number of piles** supporting the platform (**Sand fill**):
- Front wall exhibited Negligible effect.
- Lateral deformation was reduced by up to 8% when increasing number of piles.
- Tie rods tension slightly reduced with the increase in number of piles.








- 1) Effect of **increasing Number of piles** supporting the platform (**Overconsolidated clay fill**):
- Front wall exhibited Negligible effect at the maximum bending zone.
- Lateral deformation was reduced by up to 14% when increasing number of piles.
- Tie rods tension was reduced with the increase in number of piles.







- 2) Effect of increasing Stiffness of piles supporting the platform (Sand fill):
  - Front wall exhibited Increase in the maximum bending zone • with the increase in piles stiffness.

56.88%

T/Tcap.


56.22%

0.55

0.555


Barrettes (1.20x2.00m)


- Lateral deformation was reduced by up to **19%** when increasing stiffness of piles.
- Tie rods tension negligibly • reduced with the increase in stiffness of piles. 🗶






- 2) Effect of **increasing Stiffness of piles** supporting the platform (**Overconsolidated clay fill**):
  - Front wall exhibited Increase in the maximum bending zone with the increase in piles stiffness.
  - Lateral deformation was reduced by up to 14% when increasing stiffness of piles.
- Tie rods tension marginally reduced with the increase in stiffness of piles.









- 3) Effect of **increasing Spacing of piles** supporting the platform (**Sand fill**):
  - Front wall exhibited an Increase in the maximum bending zone with an increased spacing of piles.
  - Lateral deformation was Increased by up to 4% when increasing spacing of piles.
- Tie rods tension negligibly reduced with the increase in spacing of piles.








- 3) Effect of **increasing Spacing of piles** supporting the platform (**Overconsolidated clay fill**):
- Front wall exhibited an Increase in the maximum bending zone with an increased spacing of piles.
- Lateral deformation was Negligibly Increased by up to 2% when increasing spacing of piles.
- Tie rods tension negligibly reduced with the increase in spacing of piles.







- 4) Effect of adjusting bearing level of piles supporting the platform (Sand fill):
  - Front wall exhibited Negligible decrease and increase when • increasing and reducing bearing level of piles by 20% respectively.


57.25%

0.56

58.28%

T/Tcap


b/B = 120% Reference (b/B = 97%)




- Lateral deformation was almost • **Unaffected** by modifying bearing level of piles by ±20%.
- Tie rods tension slightly reduced . with the **increase** in bearing level of piles.



- 4) Effect of **adjusting bearing level of piles** supporting the platform (**Overconsolidated clay fill**):
  - Front wall exhibited Negligible effect when modifying bearing level of piles by ±20%.
  - Lateral deformation was almost Unaffected by modifying bearing level of piles by ±20%.
- Tie rods tension negligibly reduced with the increase in bearing level of piles.









5) Effect of **adjusting elevation** of the **Platform** supported on piles (**Sand fill**):

 Front wall exhibited a <u>significant increase</u> when changing the level of the platform from the typical location (Lining with capping beam).







- Lateral deformation was slightly increased by adjusting level of the platform by up to 4%.
- Tie rods tension marginally reduced with the modification in platform level.



5) Effect of **adjusting elevation** of the **Platform** supported on piles (**Sand fill**):

- Front wall exhibited a <u>significant increase</u> when changing the level of the platform from the typical location (Lining with capping beam).
- Lateral deformation was negligibly increased by adjusting level of the platform by up to 1%.
- Tie rods tension marginally reduced with the modification in platform level.





. . . . . . .



. . . . . .

. . .

#### **Conclusion and recommendation**

Increasing number of piles supporting the platform	<ul> <li>Unfavorable to the front wall (Negligible effect).</li> <li>Slightly favorable to the tie rod tension.</li> <li>Recommended to use <u>only two piles rows</u> to support the platform.</li> </ul>
Increasing stiffness of those piles	<ul> <li>Unfavorable to the front wall (Increased forces).</li> <li>Slightly favorable to the tie rod tension.</li> <li>Recommended to use reduced pile stiffness to support the platform in accordance with the design.</li> </ul>
Increasing spacing of those piles	<ul> <li>Unfavorable to the front wall (Increased forces)</li> <li>Slightly favorable to the tie rod tension.</li> <li>Recommended to use spacing of maximum 5*piles diameter (5D) to support the platform.</li> </ul>
Adjusting bearing level of those piles	<ul> <li>Unfavorable to the front wall (Negligible effect).</li> <li>Slightly favorable to the tie rod tension, slightly decreased tension with the increase in bearing Lv.</li> <li>Recommended to use the bearing level which is only suitable for the design.</li> </ul>
Adjusting the elevation of the platform	<ul> <li>Unfavorable to the front wall (Severely increased forces, i.e., Sensitive to the platform location).</li> <li>Slightly favorable to the tie rod tension. (marginal decrease effect with the adjustments).</li> <li>Recommended to align the bottom level of the platform with that of the capping beam.</li> </ul>





The International Maritime Transport and Logistics Conference "MARLOG 13"

Thank You

